BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT14494

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Improvements to roads and drains at Anjandri layout in ward no. 06, Byatarayanapura sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of RAMESH Y B		
				In Figures		In Words
1	162.68	KSRRB 300-2 : Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	cum	89.81	14610.29	Rupees Eighty Nine and Eighty One Paise Only
2	332.10	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick	Sqm	340.01	112917.32	Rupees Three Hundred Forty and One Paise Only
3	2850.00	KSRRB 500-3: Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100m, sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries complete as per specifications.	Sqm	72.06	205371.00	Rupees Seventy Two and Six Paise Only
4	427.50	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification	Cum	1109.83	474452.33	Rupees One Thousand One Hundred Nine and Eighty Three Paise Only
5	2850.00	KSRRB 500-1. Cleaning the existing WBM/WMM road surface including removing of binding materials and other foreign matter with wire brushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air, to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	10.42	29697.00	Rupees Ten and Forty Two Paise Only
6	2850.00	KSRRB 500-4: providing and applying primer coat from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specificationsDo- Medium Porosity MORTH chapter 5,	Sqm	140.65	400852.50	Rupees One Hundred Forty and Sixty Five Paise Only
7	71.25	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications.	Cum	9881.55	704060.44	Rupees Nine Thousand Eight Hundred Eighty One and Fifty Five Paise Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು 23/3/16
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of RAMESH Y B		
				In Figures		In Words
8	162.68	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	cum	71.98	11709.71	Rupees Seventy One and Ninety Eight Paise Only
					1953670.58	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

23/3/16

23/03